



A SunCam online continuing education course

Precast Segmental Bridge Construction

Part 4 - Balanced Cantilever Erection Method

by

John E. Kristensen PE., PLS., PMP.



Precast Segmental Bridge Construction
Part 4 - Balanced Cantilever Erection Method
A SunCam online continuing education course

Introduction



The popularity of precast concrete segmental bridge construction has grown worldwide in the last few decades. A broader understanding of these structures and basic outline of the processes for Precast Manufacturing, Substructure Erection, Superstructure Erection – Span by Span Method, and Superstructure Erection – Balanced Cantilever Method are detailed in the SunCam course; ***Precast Segmental Bridge Construction – An Introduction***. This course gives a more specific look at the Balanced Cantilever Method of superstructure erection. Some of the material from the referenced Introduction course is repeated within this course as background information to allow this document to be read as an individual subject. However, as the subsequent courses are added (Precast Substructures, Span by Span Erection, Segment Casting and Storage, Stressing and Grouting, etc.), each one should be complementary to provide



Precast Segmental Bridge Construction
Part 4 - Balanced Cantilever Erection Method
A SunCam online continuing education course

the full scope of this type of construction. The course will be broken down into four basic sections: Erection Equipment, Lifting and Transporting Segments, "Table Top" Fabrication and Erection, Erection Geometry, Balanced Cantilever Erection, and Stressing and Grouting.



Precast Concrete Segmental Bridges offer many benefits to owners like reduced costs, reduced construction time, reduced environmental impacts, and reduced maintenance of traffic. These benefits can be achieved while utilizing local labor and materials, better means of quality control, and with minimum requirements for future maintenance. They also offer additional structural advantages of durability, fire resistance, deflection



Precast Segmental Bridge Construction
Part 4 - Balanced Cantilever Erection Method
A SunCam online continuing education course

control, better rider serviceability, insensitivity to fatigue, and other redundancies. These bridges can accommodate highways, railways, and rapid transit, in both urban and rural environments. They can be straight or curved alignments, and can provide long spans for difficult obstructions and terrain. The Balanced Cantilever method of erection is mostly independent of the local environment making it a more versatile procedure for construction of this type of bridge superstructure than other methods that require temporary supports and bracing.

Balanced cantilever superstructure erection is a method of construction where span elements are erected in their permanent location starting at a central point and working cantilevered incrementally both up-station and down-station in a self-supporting balanced state. The segments can be placed individually alternating temporarily unbalanced to balanced conditions (the designer will specify how many elements out of balance can be erected – usually no more than one) or lifted in pairs, one over each end. This method is used for precast segmental bridge spans ranging from 150 to 500 ft. Similar to other segmental construction operations, efficiency is gained due to the repetitive assembly line nature of the work but, this method of erection is more adaptable than other methods like span by span. Although variations in span length and span height, the terrain being spanned, and changes in alignment will be less efficient than straight, constant, and accessible designs, balanced cantilever spans are well suited for curved alignments, congested project sites, rough and water terrain, rail crossings, and environmentally sensitive areas.



Precast Segmental Bridge Construction
Part 4 - Balanced Cantilever Erection Method
A SunCam online continuing education course

Erection Equipment



The Balanced Cantilever Method is highly technical and the erection is aided/accomplished with some very specialized equipment. First the segments of the span must be temporarily held in place until they are self-supporting. For most of the segments the equipment used to lift the segments into position will accomplish the task. For the table top Segments and any segments requiring closure pours, temporary supports such as, shoring towers, frames, and strongbacks will be needed. Second the segments must be lifted into position. Where access permits, ground based or barged cranes can be used to lift the segments. Excessive heights or height restrictions may limit the use of cranes so specialized gantry transports may be necessary. Specialized lifting frames will be needed to handle the weights and adjust for position when setting



Precast Segmental Bridge Construction
Part 4 - Balanced Cantilever Erection Method
A SunCam online continuing education course

each segment. Lastly, jacks, winches, cable pushers and tuggers, stressing platforms, and C-brackets are a partial listing of miscellaneous equipment and fabrications that need to be procured prior to beginning the erection.

TEMPORARY SUPPORT EQUIPMENT

The first starter segments of a span over the pier, commonly referred to as the “table-top”, will need to be supported. If the segments are on bearings, shoring towers will need to be erected along both the up-station and down-station sides of the pier column to temporarily hold the span against overturning until complete. If the segments are fixed to the columns, a frame will be needed to hold the segments in place until post-tensioning can be installed to integrate the superstructure and substructure units.

Individual Shoring Towers: The towers can be placed under each segment (either under soffit or underwing) or a combination of towers and carrier beams can be used for multiple segments. Each tower will be located horizontally and vertically for the bridge alignment and the ability for adjustment will be needed after the segments are set. Also, poor ground bearing capacity, excessive span heights, and difficult terrain or obstructions will limit this option. However, shoring towers are the most readily available materials and usually the cheapest system to purchase.

Fixed Column Frame: The frames will need to be designed to carry the weight of the table-top segments and associated construction loads. Since the frames are mounted to the columns, methods for anchoring the frames must be coordinated with the column designer and fabricator/builder (precast vs cast-in-place). These frames are individually designed project by project to accommodate specific segment weights and geometry. The project schedule and budget must account for design, fabrication, delivery, and erection.



Precast Segmental Bridge Construction
Part 4 - Balanced Cantilever Erection Method
A SunCam online continuing education course



Strongbacks: Any segments requiring a closure pour that cannot be supported from below using shoring towers will need to be hung in place using strongbacks until the closure pour concrete is hardened and the post-tensioning steel is stressed. Strongbacks are steel beams which are anchored to the previously erected superstructure elements and hold the subsequent segment in a cantilevered position.





Precast Segmental Bridge Construction
Part 4 - Balanced Cantilever Erection Method
A SunCam online continuing education course

SEGMENT PLACING EQUIPMENT

Cranes: Where access allows, cranes can be used to lift, hold, and place segments into temporary and permanent positions. Excessive heights, excessive weights, congested sites, or difficult terrain may limit this option. Each crane manufacturer and type will have specific load charts that detail the crane capacity at various boom lengths and swing radii. Allowable soil bearing capacity is a significant factor when selecting this placement method, unstable foundations can fail causing reduced crane capacity. Suitable cranes (200 to 300 ton crawlers usually) can lift the segments into place from below. Ground or barge mounted cranes do not add any additional loads to the cantilevered structure but this method will be hard to coordinate in sensitive areas or where heights and weights are excessive.





Precast Segmental Bridge Construction
Part 4 - Balanced Cantilever Erection Method
A SunCam online continuing education course






Precast Segmental Bridge Construction
Part 4 - Balanced Cantilever Erection Method
A SunCam online continuing education course

Segment Loaders: Alternatively, project size and schedule may require the design and purchase of specialized erection equipment. Segment loaders are specifically manufactured to lift and place segments. Beam and winch systems, fixed or travelers, are types of segment loaders that can be used to hoist the segments into position from above. These systems are usually slower than cranes, custom built for single use (scheduling and cost considerations), and impart very heavy eccentric equipment loads to the structure. Because these pieces are usually project specific, they will require manufacturing time and upfront money, but through economy of scale, they can pay for themselves (especially in difficult erection environments that restrict crane usage).

With either crane or winch methods, the segments will be lifted with a specialized picking beam capable of holding the segments in the various longitudinal and transverse orientations (usually through hydraulic adjustments). Lastly, stair towers and stressing platforms will be needed to provide personnel access to the top and interior of the structure.

MISCELLANEOUS EQUIPMENT



Picking Frames – Manually adjusted by threaded rods to manipulate transversely and longitudinally to adjust the lift to the proper alignment for placement





Precast Segmental Bridge Construction
Part 4 - Balanced Cantilever Erection Method
A SunCam online continuing education course


Picking Beams – Remote controlled hydraulics manipulate transversely & longitudinally to adjust the lift to the proper alignment for placement






Precast Segmental Bridge Construction
Part 4 - Balanced Cantilever Erection Method
A SunCam online continuing education course

Stressing Platforms – Provides access to upper and lower flanges for post-tensioning and grouting operations





Precast Segmental Bridge Construction
Part 4 - Balanced Cantilever Erection Method
A SunCam online continuing education course





Precast Segmental Bridge Construction
Part 4 - Balanced Cantilever Erection Method
A SunCam online continuing education course

Stair Towers – Provide access to superstructure deck from isolated areas





Precast Segmental Bridge Construction
Part 4 - Balanced Cantilever Erection Method
A SunCam online continuing education course

Lifting and Transporting Segments



Depending on the location of the storage area to the bridge erection site, the method of transportation will differ. Whether it is by trucks (on and off road), rail, or barge, several factors apply to all: hauling restrictions – time and weight, permits, environmental and noise ordinances, and distance. The most direct routes might not be the most cost effective or available. A necessary decision will also include whether to purchase, rent, or subcontract the loading and transporting. The lifting and handling of these large castings is specialized work and any errors can be catastrophic therefore, the services of professionally experienced subcontractors are advised.

Note: the segments must be transported to the bridge for erection in the same relation as they were cast.



Precast Segmental Bridge Construction
Part 4 - Balanced Cantilever Erection Method
A SunCam online continuing education course




Crane lifting segments using picking frames and picking beams with anchors or sleeves





Precast Segmental Bridge Construction
Part 4 - Balanced Cantilever Erection Method
A SunCam online continuing education course

Gantries lifting segments using under wing straps with softeners at the concrete edges






Precast Segmental Bridge Construction
Part 4 - Balanced Cantilever Erection Method
A SunCam online continuing education course



Specialized multi-axle trailers will be needed for hauling the segments, as well as, a tractor with enough horse-power to tow the load. The above trailer is adequate for non-permit loads for hauling onsite or at the casting yard. Multi-axle dollies will be needed for legal permit loads on public roadways. If the trailers are used to deliver segments over the previously constructed portions of the bridge, the engineer will need to check that the wheel and axle loads are allowable. If manufacturing details for the tractor and trailer are available, the engineer can determine the optimal location for placing each segment on the trailer to distribute the loading acceptably to each axle. Alternately, portable truck scales can be used to measure the actual axle loads and through a series of “trial-and-error” segment placements, so an optimal location can also be determined.



Precast Segmental Bridge Construction
Part 4 - Balanced Cantilever Erection Method
A SunCam online continuing education course



A loading sequence will be developed for barging segments. If the barge is not uniformly loaded it can cause an unsafe condition which may damage the segments or jeopardize the entire load. Segments will be loaded and unloaded in a specific order and location to match the barge capacities and the erection sequencing. A deep water bulkhead will allow the crane to position as close as possible to the segments and minimize the lifting radius. Alternatively, a straddle lift can transport the segments on finger piers and place the segments on a barge positioned in the berth.



Precast Segmental Bridge Construction
Part 4 - Balanced Cantilever Erection Method
A SunCam online continuing education course

Table-top Fabrication & Erection

The pier segments for a balanced cantilever bridge span are usually the largest, heaviest, and most complicated segments of a precast segmental bridge. They may be cast-in-place, precast, or a combination precast shell with cast-in-place elements. The weight of the interior diaphragm of the segment is an important factor in which type of segment is used. If schedule allows, a cast-in-place pier segment will minimize the concerns for transportation and loading of these heaviest pieces. Precasting the segment may be the only option if the schedule does not allow for forming, placing, and curing a cast-in-place segment. In this case it may be necessary to split the segment into smaller sections and/or add cast in place elements depending on the capacities of the lifting and transporting equipment.

As previously stated, if the segments are on bearings, shoring towers will need to be erected along both the up-station and down-station sides of the pier column to temporarily hold the span against overturning until complete. If the segments are fixed to the columns, a frame will be needed to hold the segments in place until post-tensioning can be installed to integrate the superstructure and substructure units. Depending on which type of bridge is designed, this will require two separate pre-erection set-ups.

If individual shoring towers are used, the ground must have a suitable bearing capacity, if not, stabilize with stone and/or use crane mats, then erect the towers to the bridge alignment and height. If a frame is used, lift the frame into position and utilizing a combination of through bolts, friction collars, and a positive connection, temporarily mount the frame to the pier column. Once the temporary supports are at the required line and grade, a complete inspection of the structure is necessary to ensure the placement of the segments are ready to proceed. The construction engineer and the support structure manufacturer should provide a checklist of safety and maintenance items to be reviewed at each setup. After a final survey to confirm all dimensions are correct, the mechanical systems used for erection adjustments should be locked down to prevent any accidental changes in alignment from occurring.


For a combination precast shell segment with cast-in-place elements on a fixed integral pier:



Precast Segmental Bridge Construction
Part 4 - Balanced Cantilever Erection Method
A SunCam online continuing education course

To begin erection, (1) set starter segments, “table-top”, on the pier column with frames or supports per the previous paragraph and align for geometry. (The full pier segment may have been split into multiple pieces due to weight considerations, if so, the pieces will be epoxied and post-tensioned together to act as a single segment). Thread post-tensioning tendons through the precast ducts while setting the segments into the frames (tendons will already be installed in the substructure elements). (2) Form and place the closure pour between the substructure and the superstructure elements (be sure to seal all post-tensioning ductwork to keep the concrete from clogging the duct or binding the tendons prior to stressing and grouting). (3) Form and place the base portion of the interior diaphragm (make sure stressing and grouting embeds are in place and sealed, threaded couplers should have been embedded in the precast shell for reinforcing bar development and installation). (4) After the cast-in-place concrete achieves the required strength, stress and grout the post-tensioning material from the substructure to integrate the table top with the substructure column and foundation (stressing and grouting is described later in the course and covered in more detail in other courses). (5) Form and place upper portion of the interior diaphragm (similar to base portion, make sure stressing and grouting embeds are in place and sealed, threaded couplers should have been embedded in the precast shell for reinforcing bar development and installation).

The pictures correspond to the numbered steps above.






Precast Segmental Bridge Construction
Part 4 - Balanced Cantilever Erection Method
A SunCam online continuing education course





Precast Segmental Bridge Construction
Part 4 - Balanced Cantilever Erection Method
A SunCam online continuing education course



Closure pours may be needed periodically through the erection to correct any unaccounted field conditions, this will help ensure errors won't be cumulative through the structure. If line can be maintained through minor shimming, these intermediate closures will not be necessary and can be closed with the end pours of the span. If the table-top is aligned within tolerances, start erecting subsequent segments otherwise, use a closure pour at this point to make corrections (this is the easiest point to make corrections to project the correct line and grade through the span). Closure pours will require a means to temporarily hang the segments in place until cast in place concrete can be formed and poured in the closure. Once all adjustments are made for line and grade, typical erection can proceed.



Precast Segmental Bridge Construction
Part 4 - Balanced Cantilever Erection Method
A SunCam online continuing education course

Since the pier segments have been fixed to the substructure any alignment issues in the substructure will be carried into the superstructure making a closure pour necessary. When this happens, strongbacks will be needed to temporarily hang the first cantilevered segments in place until the closure pour concrete cures and the temporary post-tensioning can be stressed to make the segments self-supporting in their cantilevered position. The sequence is as follows: (1) Using high strength threaded rods, anchor the strongbacks to the pier segments. (2) Lift the cantilevered segments and hang them from the strongbacks. (3) Using the geometry control data from the segment casting yard, adjust the two segments to the correct line and grade. (4) Form and place the closure pour between the segments (make sure stressing and grouting embeds are in place and sealed). (5) Once the concrete has attained the required strength, high strength threaded rod will installed through the segments and tensioned to provide the compressive load required for erection, and at this point if the design requires, cantilever tendons will be installed and stressed in the top flange of the segment.

The pictures correspond to the numbered steps above.





Precast Segmental Bridge Construction
Part 4 - Balanced Cantilever Erection Method
A SunCam online continuing education course



At this point, the “table top is complete, self-supporting, and set to the correct line and grade. The typical balanced cantilevered erection can begin.



Precast Segmental Bridge Construction
Part 4 - Balanced Cantilever Erection Method
A SunCam online continuing education course

Erection Geometry



Geometry Control for the erection process is necessary to ensure that the segments of the spans are oriented in the correct horizontal and vertical alignments, as well as, control for cross slope super-elevations. In addition to the geometry control needed for the bridge design alignment, the balanced cantilever erection method requires additional geometry control to account for the temporary construction loads on the structure caused while the span is in the cantilevered condition. Additional camber must be built into the segments. This camber will flatten out as the cantilever lengths increase. The segments are surveyed and placed in their as-cast alignment, then adjusted for any field conditions that deviate. The erection should follow the values as-cast. Minor deviations should be expected and are easily adjusted. More severe adjustments may occur and should be addressed by the engineer on a case-by-case basis.

In order to understand the geometry control for erection, a brief overview of the casting geometry is necessary (for further detail a subsequent course will detail the casting geometry more in-depth). For this course the precast segments will be short-line



Precast Segmental Bridge Construction
Part 4 - Balanced Cantilever Erection Method
A SunCam online continuing education course

match-cast. This means the segments are cast sequentially in a single stationary form system where subsequent segments are cast against their predecessor creating a matching pair. The exact bridge geometry is established between the matched pairs such that the segment is unique to a singular place in the structure. The controlled setting of the precast yard allows production similar to an assembly line environment with the goal of completing a segment each day per cell.

After casting a segment, the previous day's production is asbuilt by the survey crews to ensure the geometry was maintained while the concrete set. If the asbuilt survey shows any deviation from the plan geometry, adjustments will be made in the subsequent castings to correct the error (minor deviations can be corrected in the next segment while more severe differences may take several segments to span the adjustment or may ultimately result in rejection of the segment making a re-cast necessary). The segment is rolled out of the forms and then set in the match-cast position for the next placement. The forms are tightened around the match-cast segment, embedded materials are placed, and the new geometry is surveyed to make the segment ready for concrete. The procedure is repeated with the match-cast segment rolled out to storage, the casting rolled out to be the new match-cast, and the cell prepared for a new casting. The as-cast survey is recorded to be given to the field surveyors at the erection site for controlling the erection alignment.

At erection the individual segments are surveyed as they are placed in the cantilevered position, then the deck is re-surveyed as a unit to confirm the alignment was maintained through the erection process. Utilizing the survey control points cast into the segment, the first segment will be set in the required location and the following segments will be surveyed as they are placed to aid the "fitting up" of the matching pairs. The geometry will be monitored with each segment placed and compared to the recorded data from the casting. Through the erection process minor changes due to field tolerances will occur. This can be controlled by adding cast-in-place closure pours between segments (usually at planned locations at the beginning, end, and midpoint segments of the span but additional closures (designed condition or field condition) are possible). Since the closures are cast-in-place, the geometry can be adjusted horizontally and vertically to accommodate transverse and longitudinal changes (further options are discussed in the typical segment erection section).



Precast Segmental Bridge Construction
Part 4 - Balanced Cantilever Erection Method
A SunCam online continuing education course

Balanced Cantilever Erection



As with other segmental bridge erection methods, the typical segment erection is a repetitive process that gains efficiency with experience and scale.

Basic steps for erecting the individual elements of the span, alternating from upstation to downstation: (1) Place epoxy on match-cast faces (epoxy acts as a lubricant and sealer to facilitate a tight fit between segments), (2) Raise balanced segments along respective sides of previous segments, (3) Connect high strength rods between segments, (4) Stress rods to provide “epoxy squeeze” to seat the segments to their match-cast (any epoxy that oozes or drips out during the squeeze will need to be cleaned) (check the post-tensioning ductwork for epoxy that squeezes into the duct and restricts the diameter) at the end of this step the segments are self-supporting, (5) Install cantilever post-tensioning tendons in the internal ductwork of the balanced



Precast Segmental Bridge Construction
Part 4 - Balanced Cantilever Erection Method
A SunCam online continuing education course

segment pair's top slab (post-tensioning for cantilevered state are in top slab, continuity tendons for span completion are in the bottom slab), (6) Stress tendons and measure elongations (discussed in stressing and grouting section), (7) At this time the ducts for the rods and tendons can be grouted but this is a time consuming step and may cause problems if the grout leaks over into future ductwork ("grout migration"). Access should be provided to grout the post-tensioning elements after the span is fully erected, (8) Check survey control for line and grade to control plumbness and rotation (geometry programs should account for erection cambers cast into the segments for cantilever), (9) If survey shows any signs of deviation from the as-cast geometry the next segment will need shimming to correct the error, (10) Repeat procedure to complete the cantilever span, (11) Cast closure pours at mainspan and backspan connections, (12) Install, stress, and grout interior and exterior continuity post-tensionings. At this point the span will no longer be cantilevered and will be a continuous span through supports.





Precast Segmental Bridge Construction
Part 4 - Balanced Cantilever Erection Method
A SunCam online continuing education course



Prior to making the final closure pours (both midspan and backspan) alignment issues can develop that cannot be corrected by shimming. In this case the cantilever tips will need to be secured and brought into alignment using strongbacks. The strongbacks are used to stabilize the cantilever ends, hang formwork and access scaffolding, and vertically align the tips. For horizontal corrections cross chains and come-alongs can bring the tips into alignment (cantilevers on bearings will correct easier than fixed column types) but remember twists in one direction will cause an equal and opposite twist at the balanced end of the cantilever. The following pictures show (1) The midspan gap between two balanced cantilevers, (2) lifting the final segment into the gap with the strongback frame assembly partially installed above, (3) Overhead view of final segment being lifted into place (note ductwork connections of the continuity post-tensioning in the bottom slab, (4) strongbacks holding final segment in place while formwork for closure pours are installed (note strongbacks are adjusted with allthread rod to align the segments vertically and a diagonal cable with a come-along aligns the tips horizontally), (5) Final segment hanging in place.



Precast Segmental Bridge Construction
Part 4 - Balanced Cantilever Erection Method
A SunCam online continuing education course






Precast Segmental Bridge Construction
Part 4 - Balanced Cantilever Erection Method
A SunCam online continuing education course



As previously stated, while the segments are being erected epoxy is applied to the match cast faces. The epoxy is used as a lubricant/sealant to aid construction and increase long term durability of the structure. When pressure is applied with temporary high strength rods for an “epoxy squeeze” to seal the joints the excess epoxy will be forced out of the joint from the compressive load.



Precast Segmental Bridge Construction
Part 4 - Balanced Cantilever Erection Method
A SunCam online continuing education course



If the span is over live traffic, private property, or environmentally sensitive areas, it is a good idea to drape netting below each joint to catch the epoxy that drips from the “squeeze” so it won’t damage anything below while it hardens (once hardened it is inert and based on owners criteria, can be left behind). If the underside of the bridge has an architectural requirement, the drips will need to be cleaned off each joint or they will harden into unwanted jagged stalactites. If too much epoxy is used on the joints, excessive amounts will squeeze out as the joints are pulled tightly together. This will affect the amount of epoxy purchased, handled, and cleaned up. If too little epoxy is used, the joints will leak which will require epoxy pressure injection sealing to repair the integrity of the corrosion/freeze/thaw protection systems. The optimal amount of epoxy per joint will be fine-tuned by experience as spans are completed.

Simple formwork elements are hung between the two segments and held in place with all-thread rods for a tight seal. High Early concrete is usually used when making a closure pour to minimize curing time to obtain the minimum compressive strength and continue operations.



Precast Segmental Bridge Construction
Part 4 - Balanced Cantilever Erection Method
A SunCam online continuing education course



Spreading epoxy lubricant/sealer between segments prior to tensioning



Forming closure pours from interior of segment box



Precast Segmental Bridge Construction
Part 4 - Balanced Cantilever Erection Method
A SunCam online continuing education course

Lastly the final posttensioning materials are installed through internal and external ductwork in the span interior. Continuity tendons in the bottom flanges are accessed through blisters formed in the floor slab of the box interior. Once stressed these tendons provide the uplift forces needed for the newly completed simple span.





Precast Segmental Bridge Construction
Part 4 - Balanced Cantilever Erection Method
A SunCam online continuing education course

Stressing and Grouting

The temporary rod post-tensioning and permanent strand tensioning operations (cantilevered tendons in the top flange) are performed as each segment is hung from the cantilevered ends. Permanent internal and external strand and rod post-tensioning (continuity tendons in the bottom flange) occurs after the span is complete. Install post-tensioning strand and rod longitudinally through the span. The number of strands per duct and the number of ducts per span will vary and a stressing sequence will be provided in order to transfer a uniform load. The strand is stressed using high strength hydraulic jacks. When the jacks reach the required pressure (compressive loads will be calculated in terms of hydraulic pressure in the jacks) the strands will be anchored in places with wedges to retain the loaded energy. The stresses applied to the strand will stretch the steel.



Elongations will be measured to ensure the stresses occurred over the entire length of the strand (a shortened elongation will mean the strand is pinched somewhere along its length and repairs may be necessary). The ducts are then pressure grouted to both



Precast Segmental Bridge Construction
Part 4 - Balanced Cantilever Erection Method
A SunCam online continuing education course

protect the strand from corrosion and to permanently contain the stresses from the jacks. Concrete is then poured around the anchor blocks for further corrosion protection. Stressing and Grouting operations are explained in more detail in the SunCam course Precast Segmental Bridge Construction – Stressing and Grouting.



Once each span is complete it will be capable of being open to traffic for the design loading.

No matter how accurate the geometry control is with casting and erecting the superstructure elements, the riding surface will be constructed by the individual segments and will reflect any imperfections across each segment joint. This will not matter for railway bridges or other structures where the segments are not the final riding surface. For bridges with rideability requirements, a longitudinal grinding is



Precast Segmental Bridge Construction
Part 4 - Balanced Cantilever Erection Method
A SunCam online continuing education course

recommended to eliminate these imperfections and a transverse grooving can be added to improve skid resistance.

Summary Conclusion

This course gives a more specific look at the Balanced Cantilever Method of superstructure erection for precast segmental bridges, broader information can be found in the SunCam course ***Precast Segmental Bridge Construction – An Introduction***. This construction is very specialized and no matter how in-depth the courses are written there is no substitute for experience. Many specialty subcontractors and suppliers offer onsite consulting services as a supplement to the construction staffing. To organize a new construction project, managers should strongly consider these additions as well as the support of an experienced construction engineering firm. The consulting experience will help train the project personnel, troubleshoot problems, and give confidence to the owner. Additionally, a well-structured quality control program is a must. From design to casting to erection, unaccounted errors can have significant impacts to cost, schedule, and **SAFETY**.

Lastly, safety must be a constant focus of every operation. Because of the versatility of these bridges (mostly described in the opening paragraphs of the course) they are often chosen to be constructed in some of the most adverse and inaccessible areas imaginable. Working with extreme weights at excessive heights requires safety diligence from every stakeholder. A comment from a past superintendent demanding patience about an operation; “we’re not just throwing pillows around”, sounds lighthearted considering the critical nature of these operations but served as a rallying cry for the safety of an entire project that completed without any OSHA recordable or lost-time incidents. Please be safe.